

**PROJECT SUMMARY** 

**SOLAR – RENEWABLE ENERGY** 

## COMMERCIAL **HEALTHCARE**

**TRAFFIC/STREET LIGHTING** 

**INDUSTRIAL** 

**INSTITUTIONAL** 

## BRANCH WEST SACRAMENTO Healdsburg WWTP Floatovoltaic Solar System GENERAL WEN LUU MANAGER **CECI PROJECT #:** \$5205033 **DURATION:** 4 months PROJECT WEN LUU 340 Foreman Lane MANAGER **PROJECT ADDRESS:** SIZE: 4.78MW DC Healdsburg, CA 95448 FOREMAN DAVID GOMES DATE OF COMPLETION : May 2021 CONTRACT: \$5,306,182



Description	<b>Installation of 4,780,600 W DC (4.7MWDC) floating solar (floatovoltaics) PV system at Healdsburg Water Treatment plant.</b> The system floats on 2 collecting ponds at the facility and consists of 11,660 – 410-Watt PV modules. Floating solar helps minimize the evaporation of the pond, helps control algae and makes use of otherwise wasted space. Designed and built by Collins. The facility has a special requirement of needing to inspect the pond liner at both ponds in a 5-year period, we designed arrays that can be decoupled and repositioned – this would allow the owners to drain the pond and inspect the liner – all while the system still produces power from the sun. At the time of completion, it was the largest floatovoltaics system in the USA.
PV Asset Owner	White Pines Renewables Evan Riley – <u>evan@whitepinerenew.com</u>   248.808.2015
General Contractor	Collins Electrical Company, Inc. 1902 Channel Drive West Sacramento, CA 95691
Architect	Collins Electrical Company, Inc. 1902 Channel Drive West Sacramento, CA 95691
Engineer	<b>PV Amps</b> Anastasisos Hionis – <u>stas@pvamps.com</u>   916.425.4056
Corporate office: 3412 Metro Dr. Stockton, CA 95215   Phone: 1-833-787-CECI (2324)   Fax: 209-466-3146	
DUBLIN · FRESNO · MARINA	